



Bedkot Municipality
Office of the Municipal Executive
Sisaiya, Kanchanpur
Sudurpashchim Province, Nepal
Bill of Quantity



Name of Project:- Bhandari Tol Pipal Chautara Najik Hume pipe Culvert Nirman & Pipal Chautara dekhi prabin sunarko Ghar samma ko bato pani pitch
Location: Bedkot-9 Kanchanpur.
Contract Identification No: BED/DP/W9/081/82-10

F/y:2082/83

S.N.	Description/Items	Quantity	Unit	Rate		Amount	Remarks
				In Figure	In words		
1	Earth work in excavation of foundation in Ordinary soil(Depth upto 3 m) of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications by Mechanical Means, Dewatering required	8.30	Cum				
2	Stone filling work in foundation trench & Levelling including 30 m lead/Used alternatively as soling	3.38	Cum				
3	P.C.C. work 1:3:6 in Foundation, Wall including 30 m lead by manual means	2.29	Cum				
4	Stone masonry work in cement mortar 1:4 including 10 m lead and 5 m lift as per Drawing and Technical Specifications.	16.06	Cum				
5	Supply and laying of RCC NP3 Class Hume pipe of diameter 1200mm and 2.5 m in length.	2.00	No.s				
6	Providing and laying natural gravel	11.20	Cum				
7	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead as per Drawing and Technical specifications & lead upto 30 m	1422.00	Sqm				
8	Providing and laying granular sub-base on prepared surface, mixing at omc, and compacting to achieve the desired density . complete as per Drawing and Technical specifications .	271.31	Cum				
Total Amount							
VAT 13%							
Grand Total Rs							

Name of Firm

Address of Firm

Authorized Signature and Date

Head of Firm

Date :