

Office of the Municipal Executive
Sisaiya, Kanchanpur
Sudurpaschim Province, Nepal

महानगरपालिका
सुदूरपश्चिम प्रदेश
काठमाडौं

(Signature)

सुदूरपश्चिम प्रदेश
काठमाडौं

कुल लागत 291896.71
आर्थिक वर्ष : २०८१/०८३

Bill of Quantity

योजनाको नाम : मल्लो पोखरी फिल्ल मर्मत
स्थान : वंदकोट नगरपालिका ०५, कंचनपुर

S. n.	Description of items	Quantity	Unit	Rate (Nrs.)		Amount (Nrs.)		Remarks
				In Figure	In words	In Figure	In words	
1	Scarifying the existing Field surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead as per Drawing and Technical specifications & lead upto 30 m	6000.00	SQM					
2	Earth work in excavation of foundation in Ordinary soil (Depth upto 3. m) of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications by Mechanical Means, Dewatering required	57.60	CUM					
3	Earth work Filling in with Ordinary soil, spreading in layers of 15/15 cm, spraying water & Manual Compaction including lead upto 10 m as per Drawing and instruction of the Engineer	270.00	CUM					
4	Transfer of Goal Post as per Instructed by site incharge with all necessary work	1.00	job					
		Total Amount						
		Vat 13%						
		Grand Total						

Name Of The Contractors
Date
Sign
Stamp