


Bedkot Municipality
Office of the Municipal Executive
Sisaiya, Kanchanpur
Sudurpaschim Province, Nepal



Bill of Quantity

कुल लागत

289190.01

अधिक बर्ष : २०८२/०८३

योजनाको नाम : मुक्ति आ.वि. पहाल मर्मत
योजना कार्यान्वयन हुने स्थल: बेदकोट नगरपालिका-०५

S.n.	Description of Items	Quantity	Unit	Rate (Nrs.)		Amount (Nrs.)		Remarks
				In Figure	In words	In Figure	In words	
1	Excavation in soft clay and silty soil having lead upto 1.0m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer	8.59	cum					
2	Stone Soiling work in foundation trench & Levelling including 30 m lead.	2.97	cum					
3	P.C.C. work 1:3:6 in Foundation, Wall including 30 m lead by manual means	5.46	cum					
4	Stone masonry work in cement mortar 1:6 including 10 m lead and 5 m lift as per Drawing and Technical Specifications.	13.04	cum					
5	Earth work Filling in with Ordinary soil, spreading in layers of 15/15 cm, spraying water & Manual Compaction.	22.44	cum					
6	(50*50*3) mm MS angle For Column	101.41	kg					

7	1.5 m Height Chain Link Fence mesh size (100*100) MS Fence For Boundary including cutting , bending ,welding ,placing all complete	141.90	kg					
8	3 nos Row Of Barbed Wire including all complete Work	132.00	Rm					
Total Amount								
Vat 13%								
Grand Total								

(Handwritten signature)

Name Of The Contractors
Date
Sign
Stamp